

Tender Schedule						
Name of Work : Construction of side Wall of Proposed Pond at MVRCRI						
Item No	Description of Work	Quantity	Unit	Rate	Amount	Remarks
1	Earth work in excavation in all kinds of soil except hard rock which requires blasting by mechanical means Hydraulic excavator/manual means in foundation trenches or drain	30.00	Cum			
2	Providing and laying in position machine batched and machine mixed design mix M-20 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, Including the cost of centering, shuttering , for DR Belt	50.00	Cum			
3	Dry rubble masonry using rubble including cost and conveyance of all materials and labour charges etc. complete.	220.00	Cum			
4	Providing and constructing Laterite masonry wall in superstructure in cement mortar 1:6 (one cement: six coarse sand) , cost of labour, materials, loading and unloading, transportation and all other incidental charges etc. complete and as directed by the Engineer-in-charge	25.00	Cum			
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, and binding using thermo-mechanically treated (TMT) bars with cost and conveyance of all materials and labour charges etc. complete	5000.00	Kgs			
6	Plastering with C.M. 1:4 (one cement four sand) 12mm thick for walls inside and outside with necessary scaffolding and thread lines, including cost and conveyance of all materials and labour charges etc. complete.	10.00	Sqm			
	Total					