



Works to be done :-

1. Remove the existing inspection chamber /Manhole 10SIC,11SIC,12WIC & 13WIC
2. Fix new PVC Inspection chambers in the above locations
3. Connect inlet and outlet pipe lines to the PVC inspection chambers
4. Provide concrete Man holes around the PVC Inspection chambers to protect them and to avoid possibility of waste water leakage to outside