

BOQ -for Fire Line Extension for PET CT room					
SL NO	DESCRIPTION	UNIT	QTY	RATE	AMT
	1)Supply, Installing, testing and commissioning of 'B' class MS pipes confirming to IS 1239, up to Dia 100mm & IS 3589 for 200mm & above ,malleable specials extruded type, such as Reducers, elbows, flanges and all required fittings. The pipes shall be spray painted with One coat each of Epoxy primer & 2 top coat Paint (Red) using approved type, Galvanized, supports at standard spacing, anchor fasteners, bolts, nuts, clamps, rails "U" & threaded bolt, Including cutting, Welding, fixing in / on walls, ceiling by using the supports etc, as per drawings.,2) Supply, Installation, Testing & Commissioning of Addressable Fire Alarm System, comprising Single-Loop Addressable Fire Alarm Control Panel, Manual Call Points (MCP), Hooter cum Strobe Sounder/Beacon, complete with necessary wiring, accessories, programming and commissioning.				
1	80mm B Class pipe	RM	6		
2	65 mm B Class pipe	RM	6		
3	50 mm B Class pipe	RM	6		
4	40 mm B Class pipe	RM	6		
5	32 mm B Class pipe	RM	45		
6	25 mm B Class pipe	RM	50		
7	80 mm BFV valve	Nos	1		
8	Alarm panel -Single loop -Cooper	Nos	1		
9	Battery 12V	Nos	2		
10	Module - Cooper	Nos	1		
11	Isolator module	Nos	1		
12	Control module	Nos	1		
13	MCP-Cooper	Nos	2		
14	Hooter/Strobe -cooper	Nos	2		
15	Smoke Detector with base -Cooper	Nos	32		
16	2 Core Armoured CU cable supply & laying	RM	180		
17	Pendant Springer	Nos	40		
18	Fire extinguisher ABC 4kg	Nos	15		
19	Fire extinguisher co2 45kg	Nos	4		
20	Fire Exit board	Nos	2		
A	Total Amount (Basic)				
B	GST @18%				
C	G-Total Including GST				